

# TNT Product Bulletin TNT

## SWING GATE WALL MOUNTED RACKS & PANELS

### 1) SWING GATE WALL MOUNTED RACKS



- 19" wide rack mounting units in 18" depth and 47", 24" height two versions.
- Front swing gate hinges from either left or right.
- Rear mounting holes provided on 16" centers for standard stud mounting and 18 5/16" centers to allow units to be mounted on a 19" rack.
- Includes equipment mounting screws and 12 reusable cable management ties.
- Mounting holes tapped #10-32 on EIA standard spacing.
- Integrated strain relief tie off points allow for flexible cable management.
- Holds up to 100 lbs capacity.
- 12 gauge steel construction.

<u>Part Number</u>	<u>Description</u>	<u>Height</u>	<u>Depth</u>	<u>Width</u>
022-SGWMR-1	Short version	24"	18"	19"
022-SGWMR-2	Tall version	47"	18"	19"

### 2) 19" EQUIPMENT RACKS



- Constructed of 6061: T6 structural-grade aluminum.
- Self supporting base: 3.5" x 6" aluminum extruded angle.
- Standard top: 1 1/2" x 1 1/2" aluminum extruded angle.
- Mounting hole pattern: EIA ( 1 3/4" ), 10-32 tapped.
- Assembly hardware included.
- Height: 84" ( 7 feet ).
- Brushed aluminum or black powder coat finish.

<u>Part Number</u>	<u>Description</u>	<u>Height</u>	<u>Width</u>
022-07	19" aluminum 7 feet high equipment rack	84"	19"
022-07-BK	19" black 7 feet high equipment rack	84"	19"



**Tri-Net Technology, Inc.**

Total Network Telesis

U.S.A.

21709 FERRERO PARKWAY  
 WALNUT, CALIFORNIA 91789  
 TEL 909-598-8818 FAX 909-594-8666  
 www.trinetusa.com info@trinetusa.com